

	operation when directly connected to chimney	operation when connected accumulation mass
Energy label	A+	A+
Operating data		
Nominal heat power	11 kW	----
Efficiency	> 80 %	----
Consumption of wood	3,2 kg/h	4,5 kg
Total heat output of the burning chamber	----	16 kW
Mass flow of flue gas	8,1 g/s	15 g/s
Required chimney pressure	12 Pa	12 Pa
Required amount of combustion air	30 m³/h	45 m³/h
Average flue gas temperature		
on the output	292 °C	310 °C
past 2,4 m of ceramic accumulation system KMS 300 ¹	----	205 °C
Heat distribution		
fireplace insert	50 %	30 %
door glass (single / double)	50 / 0 %	50 / 0 %
adjoining accumulation mass	----	20 %
Information for ventilated builds		
Minimal grill area supply / outgoing	700 / 850 cm²	700 / 850 cm²
Minimum distance from insulated areas / floor	50 / 0	50 / 0
Reference insulation ² ceiling / back wall / side wall / floor	120 / 80 / 0 / 0	120 / 80 / 0 / 0
Calciumsilicate insulation ³ ceiling / back wall / side wall / floor	80 / 60 / 0 / 0	80 / 60 / 0 / 0
Information for non-ventilated builds (closed grills)		
Minimum radiant area ⁴	4,5 m²	4,5 m²
Minimum distance from insulated areas / floor	50 / 20 mm	50 / 20 mm
Reference insulation ² ceiling / back wall / side wall / floor	160 / 100 / 0 / 20 mm	160 / 100 / 0 / 20 mm
Calciumsilicate insulation ³ ceiling / back wall / side wall / floor	120 / 75 / 0 / 20 mm	120 / 75 / 0 / 20 mm
General technical information		
Total weight / lining weight	ca. 236 / 43 kg	ca. 236 / 43 kg
Burning chamber dimensions (width x depth)	280 x 410 mm	
Combustion air connection	Ø 150 mm	
Use in non-ventilated accumulation builds according to craft rules	suitable	
Tested according to	EN 13229	
Meets values	BImSchV (Stufe2), 15a BVG	

¹ Listed value from testing. For accurate results is evaluation of each system in the Ortner / KOV program necessary.

² Mineral wool according to AGI-Q 132

³ Example SkamoEnclosure Board 225 kg/m³


⁴ Depends on accumulation period and material characteristics. Listed values calculated with chamotte stone thickness 30 mm with radiant area 500 W/m²

UKA 56/50/56/52

Technical data
Version 2019/08

air connection / feet

M 1:10




UKA 56/50/56/52

Technical data
Version 2019/08

air connection / feet

M 1:10




UKA 56/50/56/52

air connection / feet

Technical data
Version 2019/08

M 1:10




UKA 56/50/56/52

Technical data
Version 2019/08

supporting construction incl. build-on frame 3sides 70 mm

M 1:10




UKA 56/50/56/52

Technical data
Version 2019/08

supporting construction incl. build-on frame 3sides 70 mm

M 1:10




UKA 56/50/56/52

Technical data
Version 2019/08

supporting construction incl. build-on frame 3sides 70 mm

M 1:10




UKA 56/50/56/52

Technical data
Version 2019/08

supporting construction incl. build-on frame 5sides 70 mm

M 1:10




UKA 56/50/56/52

Technical data
Version 2019/08

supporting construction incl. build-on frame 5sides 70 mm

M 1:10




UKA 56/50/56/52

Technical data
Version 2019/08

supporting construction incl. build-on frame 5sides 70 mm

M 1:10




UKA 56/50/56/52

Technical data
Version 2019/08

supporting construction incl. build-on frame 8sides 70 mm

M 1:10




UKA 56/50/56/52

Technical data
Version 2019/08

supporting construction incl. build-on frame 8sides 70 mm

M 1:10



UKA 56/50/56/52

Technical data
Version 2019/08

supporting construction incl. build-on frame 8sides 70 mm

M 1:10

